



By Tymetal Corp.

678 Wilbur Avenue

Greenwich, NY. 12834

Phone: 518-584-4400 Fax: 518-584-6630

LIST PRICE -TARCO® LEAF COLLECTION BOX WITH FLEXIBLE CONNECTOR

DIMENSIONS: 76-3/4" WIDE, 68-3/4" HIGH, SEE CHART BELOW FOR LENGTH.

CONSTRUCTION: THE SIDES, FRONT AND REAR DOOR OF THE LEAF BOX SHALL BE OF 10-GAUGE STEEL CONSTRUCTION, ADEQUATELY BRACED, ELECTRICALLY WELDED AND HAVING SMOOTH INTERIORS.

REAR DOOR: SHALL BE FULL OPENING, HINGED AT THE TOP BY PINS OF NOT LESS THAN 3/4", A POSITIVE LOCK MECHANISM SHALL OPERATE FROM THE GROUND.

MOUNTING EQUIPMENT: TWO FORWARD MOUNTED ANCHORING CHAINS HAVING A COMBINED TENSILE STRENGTH RATING OF NOT LESS THAN 110,000 PSI SHALL BE PROVIDED TO PREVENT THE LEAF BOX FROM SLIDING BACK WHEN TRUCK FLOOR IS ELEVATED.

EXHAUST SCREENS: THE EXHAUST SCREEN SECTIONS SHALL BE CONSTRUCTED OF ANGLE IRON FRAMED AND EXTERNALLY REMOVABLE WITHOUT REQUIRING ACCESS TO THE INTERIOR.

BAFFLE: AN INTERIOR RUBBER BAFFLE DEFLECTOR SHALL BE SUPPLIED TO DISTRIBUTE THE LEAVES IN THE BOX PROPERLY.

FLEXIBLE CONNECTOR: A SELF-SEALING CONNECTION FOR THE LEAF BOX INSTALLATION SHALL PROVIDE FOR VERTICAL, HORIZONTAL, AND LONGITUDINAL MOVEMENT OF THE LEAF LOADER DISCHARGE DUCT WITHOUT THE USE OF A HOSE. THE FLEXIBLE CONNECTION SHALL INCORPORATE IN ITS DESIGN A HEIGHT ADJUSTABLE, 18" WIDE DISCHARGE DUCT REST. DUCT REST TO BE CONSTRUCTED OF 12 GAUGE STEEL.

PAINT: TARCO ® YELLOW, TARCO ® WHITE, OMAHA ORANGE OR INDUSTRIAL GLOSS BLACK.

<u>CUBIC YARD CAPACITY</u>	<u>LENGTH</u>	<u>LIST PRICE</u>
9.3	8'2"	\$9,836.40
10.5	9' 2"	\$10,449.60
11.7	10' 2"	\$11,058.60
12.9	11' 2"	\$11,670.40
14.1	12' 2"	\$12,280.80
15.3	13' 2"	\$13,503.00
16.5	14' 2"	\$14,611.80

LEAF BOX FLOOR (REQUIRED FOR UNFLAT FLOORS) +\$1,190.00
MESH DUST TARP+\$499.80
DUMP BODY HOLD EQUIPMENT (SHIPPED LOOSE).....+\$245.00

*THESE ARE FOB GREENWICH, NY LIST PRICES. NEED TO INCLUDE FREIGHT.
PLEASE NOTE THAT BOXES ARE DELIVERED ASSEMBLED. FLEXIBLE CONNECTOR SHIPPED LOOSE. THESE BOXES CAN ALSO BE USED AS CHIPPER BOXES (REMOVAL OF REAR RUBBER CONNECTOR ASSEMBLY REQUIRED).